

# Charles Universal Broadband Enclosure CUBE-PM63912JM3

# **General Description and Installation**

1.	GENERAL INTRODUCTION	1
	1.1. Document Purpose	1
	1.2. Product Purpose	
	1.3. Product Mounting and Location	
2.	PRODUCT DESCRIPTION	
3.	INSTALLATION	
٠.	3.1. Inspecting the Product	
	3.2. Following and Using Safety Precautions	
	3.3. Obtaining Tools and Equipment	
	3.4. Preparing the Installation Site	
	3.5. Lifting the CUBE	
	3.6. Mounting the CUBE	
	3.8. CUBE Wiring and Equipment	
	3.9. Conduit Seals	
	3.10. Verifying the Installation	
4.	PERIODIC MAINTENANCE	
5.	TECHNICAL ASSISTANCE AND REPAIR SERVICE	
6.	WARRANTY & CUSTOMER SERVICE	
7.	SPECIFICATIONS	10
	7.1. Regulatory Specifications	10
	7.2. Product Specifications	
	7.3. Macro Alarm Panel Connections	




Figure 1 Front View of the CUBE

## 1. GENERAL INTRODUCTION

## 1.1. Document Purpose

This document provides general information for the CUBE-PM63912JM3 of the Charles Industries' Universal Broadband Enclosure (CUBE) product line. Figure 1 shows a closed front view of the enclosure.

-NOTE-

Hereafter, the Charles Universal Broadband Enclosure CUBE-PM63912JM3 will be referred to as the "CUBE."

#### 1.2. Product Purpose

The CUBE consists of a protective enclosure for an integrated system of electronic components and equipment that can serve fiber and copper interfaces.

## 1.3. Product Mounting and Location

This enclosure is suitable for outside plant-type (OSP) locations and those that may require NEC compliance. The outdoor, weather-resistant CUBE is to be mounted on a concrete pad or steel grate platform. The installer connects the power, fiber, and copper connections. Detailed mounting and installation information is covered in Section 3.



## 2. PRODUCT DESCRIPTION

The CUBE is a single compartment that includes 39 RU of 23" horizontal rack space, a side-mounted 4k BTU HVAC system, a 12-position AC load center, a 120V UPS, and a 120V battery pack.

Figure 2 shows the CUBE dimensions. Figure 3 shows the main components of the CUBE.




Figure 2 CUBE Dimensions (in inches)

Page 2 of 11 2<sup>nd</sup> Printing






Figure 3 CUBE Components

2<sup>nd</sup> Printing Page 3 of 11



#### 3. INSTALLATION

## 3.1. Inspecting the Product

The CUBE is shipped mounted upright on a skid. Remove the bolts, unpack the unit, and dispose of the packaging material.

#### -INSPECTION NOTE-

Visually inspect the unit for damages prior to installation. If the equipment was damaged in transit, immediately report the extent of the damage to the transportation company.

## 3.2. Following and Using Safety Precautions

Read the following site and safety tips, cautions, and warnings, then proceed with the paragraphs that follow.

- For installation, follow all National Electrical Codes (NEC) ANSI/NFPA 70, local, environmental, workplace, and company
  codes, safety procedures, and practices.
- Minimum spacing between the accessories and components and the housing for ITE equipment shall be maintained for safe operation of the equipment when installed in accordance with NEC ANSI/NFPA 70.
- Read all instructions, warnings and cautions on the equipment and in the documentation shipped with the product.
- Always connect ground connections first.
- Do not place this product on weak or unstable surfaces which may allow the product to fall, resulting in potentially serious damage(s) to persons or product.
- Only authorized trained personnel shall install the CUBE.
- In windy conditions, be sure to engage the wind latches to secure the door in a stationary position.

### 3.3. Obtaining Tools and Equipment

Obtain the following recommended or needed items for installing the CUBE.

- Sufficient length and quantities of fiber cable (or pigtails)
- Cable scoring, opening, and cutting tools for cable sheathing, shields, wrappings, strength members and buffer tubes
- Wire strippers
- Crimpers
- Cable, tube, wire, and fiber cleaning materials
- Protective and/or insulated work gloves
- Safety glasses
- Tape measure
- Marking utensil
- #6 ground wire or rod and earth ground materials
- Bond strap (optional, from cable bond clamp to bond post)
- Any exterior cable strain relief, per company practice
- Slotted, hex, and Phillips screwdrivers
- Torque wrench
- Assorted cable ties, clips, or fasteners (optional)
- Can wrench (216 type tool)
- Derrick for lifting
- Level

## 3.4. Preparing the Installation Site

Observe the following site preparation recommendations.

- Leave adequate horizontal and vertical space between multiple installations to allow for proper cable access, as well as enough room around the enclosure to open the door(s).
- The site must meet minimal personnel and equipment safety requirements.
- The distance from the cable entry point should be consistent with local installation practices.
- The pad or platform must be able to support the weight of the CUBE.
- Run all fiber and copper facilities to the site.



## 3.5. Lifting the CUBE


See Table 1 for CUBE weight. Charles recommends the following procedure for lifting the CUBE.

## 3.5.1. Required Equipment

- One derrick (crane) capable of lifting the CUBE
- Four lifting slings or chains with each having a 2,500 lbs. capacity
- Connecting links to attach slings to the CUBE's lifting hoists
- 75-ft. long tagline rope

Insert the lifting sling connecting links securely through each of the lifting hoists as shown in Figure 4. Ensure that the lifting chain is at least 32" long and meets the CUBE at a 60° angle

## 3.5.2. Warnings and Specific Safety Precautions



Observe the following local safety procedures when performing the tasks in this section.

- Keep the CUBE away from any power lines.
- Keep bystanders away from the work operations at all times.
- Only trained operators shall operate the crane for lifting and setting the CUBE.
- Do not suspend loads over people or equipment.
- All persons working with hoisting equipment shall wear standard safety gear according to local practices including safety helmets and steel-toed shoes.
- Do not operate the hoisting equipment until all stabilizers are extended and in firm contact with the ground or adequate support structure.
- Do not attempt to retract or extend the stabilizers while a load is suspended.

## 3.6. Mounting the CUBE

The CUBE can be mounted on a new or existing concrete pad. A gasket is affixed to the bottom of the CUBE for mounting on concrete. If the gasket becomes damaged during installation, order a replacement under part number 80-006688-A. Ensure that the unit is level.

#### 3.6.1. Torque Requirements

Torque all hardware as shown below (unless otherwise noted). These values apply to SAE Grade 1 & 2 Low Carbon Steel, ASTM A307 Low Carbon Steel, and Stainless Steel Grade 18-8.

Thread Size	In-lbs	Ft-lbs
4-40	4±10%	
6-32	8±10%	
8-32	16±10%	
10-32	26±10%	
12-24	50±10%	
1/4-20/M6	60±5%	5±5%
5/16-18	125±5%	10.4±5%
3/8-16	180±5%	15.0±5%
1/2-13	500±2%	41.7±2%
5/8-11	1000±1%	83.3±1%





Figure 4 Lifting the CUBE

2<sup>nd</sup> Printing Page 5 of 11



#### 3.6.2. Constructing a New Pad

- Use only concrete for new pad construction. Do not use substitute materials since they lack the rigidity for CUBE placement.
- Observe local building practices for pad construction. Charles recommends that the pad should extend a minimum of 8" beyond the CUBE base on all sides.
- Use a minimum of 6" of sand or gravel as a base for the pad for leveling purposes.
- Figure 5 shows the required conduit openings and mounting hole dimensions for entering/mounting the bottom of the CUBE. Use these dimensions when designing the pad.






Figure 5
Mounting Hole Dimensions (in inches),
Top View

### 3.6.3. Mounting the CUBE on a Pad

Eight customer supplied, corrosion resistant, 1/2"-13 hex head bolts with anchors are required for mounting the CUBE to the concrete pad. Use the following steps to mount the CUBE to a pad.

- 1. Layout, drill, and set the 1/2" anchors per manufacturer's recommendations. The embedment depth is not to exceed 3.5".
- 2. Clean any debris from the concrete pad.
- 3. Open the equipment chamber door to allow access to mounting holes.
- 4. Ensure that the CUBE is parallel to the pad surface as it is placed onto the pad and that it aligns with the holes in the pad. Dress the cable/conduit so that it aligns with the CUBE openings as it is lowered onto the pad.
- 5. Place the CUBE on the pad. Loosen the slings so that all the weight is on the pad. Check that the CUBE is properly aligned.
- 6. Secure the CUBE to the pad using the 1/2"-13 hex head bolts. Tighten all bolts securely.
- 7. To secure the CUBE to a steel grate platform, install 1/2" corrosion-resistant Grade 5 steel hardware through the cabinet and platform grate. Ensure that the bolts are long enough to extend past the nut on the bottom side of the platform grate. For all mounting applications, each bolted joint should have a minimum Ø1 inch fender washer on the inside of the cabinet (and underside of the platform grate for platform mounting) with a lock washer. The washer on the underside of the platform must be large enough to cover both adjacent bearing bars as shown in Figure 6.
- 8. Once the CUBE is secured, remove the slings and tagline. Close the door.




Figure 6 Installing on a Platform

Page 6 of 11 2<sup>nd</sup> Printing



## 3.8. CUBE Wiring and Equipment

After the CUBE is properly mounted in the desired location, apply No-Ox where bus bar and other 2-hole lug connections will be made. Install ground and power connections. Always ground the equipment first, before making any other connections.

MARNING Perform all bonding and grounding connections prior to any electrical and communications connections.

In order to prevent condensation prior to being placed in service, do not remove the desiccant until the CUBE is sealed and power is applied. A basic electrical diagram is shown in Figure 7.




Figure 7 Electrical Diagram

2<sup>nd</sup> Printing Page 7 of 11



#### 3.8.1. Ground Connection

Use the two 2x8 position ground bars provided in the equipment compartment for all grounding of internal equipment. Stack hardware as shown in Figure 8. External ground lugs are available on the sides of the battery compartment for connecting a site ground wire.

### 3.8.2. AC Voltage Connection

The incoming AC voltage is a single phase 208/240V at 60Hz and is connected to the 100A main circuit breaker in the AC load center. The maximum wire size is 2/0AWG. The installer connects the two hot (line) wires to the breaker, the neutral wire to the neutral bus and the ground wire to the ground bus. Use wire that is sized per National Electrical Code NFPA70 table 310.16.




Figure 8 Ground Bar Hardware Stack

The CUBE is normally powered from the 208/240VAC from the utility. In the event of a power outage, an external 50A generator can be connected to the generator inlet. The generator inlet uses the 2-pole 50A breaker in the load center. When power from the main utility is off, slide the main breaker to the "OFF" position. If necessary, reposition the manual transfer switch in the load center into the generator position, and turn on the generator breaker. When power from the main utility is restored, slide the generator breaker into the "OFF" position, slide the manual transfer switch back to the normal position, and turn the main breaker back on.

#### 3.8.3. HVAC Operation

The 4000BTU AC powered HVAC is driven by a built-in controller and temperature sensor. The factory cooling cycle turns on at 30°C and off at 27°C. The heating cycle turns on at 10°C and turns off at 15°C. The CUBE is equipped with a cutoff switch that shuts off power to the HVAC compressor when a door is opened to minimize condensation buildup on the coils. See the label on the HVAC for firmware information. For further information, refer to the HVAC documentation that ships with the CUBE.

#### -NOTE

Changing the cooling or heating cycles' default factory set points can lead to system performance issues, such as equipment failures, increased power use, unnecessary alarms, noise, condensation build up, compressor or fan failure caused by excessive runtimes and vibration.

Avoid placing items in front of the HVAC's return and supply vents. Maintain a minimum of 6" clearance to enable proper air flow.

#### 3.8.4. Overheat Thermostat

The CUBE is equipped with an overheat (high temperature) alarm thermostat in the equipment compartment that provides a normally closed connection. The overheat alarm is factory set at 50°C and opens the connection if this temperature is exceeded.

#### -NOTE-

Changing the overheat (high-temp) thermostat default factory set points can lead to unnecessary alarms or system performance issues, such as equipment failures as a result of unreported alarms.

#### 3.8.5. Macro Alarm Terminal Panel

An integrated macro-site alarm panel is mounted on the left wall of the cabinet. This panel provides forty protected dry contact alarm inputs to screw down terminals or 66-block connections (Figure 9).

The cabinet comes with a standard alarm schedule label (See Table 2). The table can be replaced or augmented to match the specific alarms being used. All connections are normally closed and open on alarm.




Figure 9 Alarm Terminal Panel

Page 8 of 11 2<sup>nd</sup> Printing



#### 3.8.6. Fiber and Copper Entry

The CUBE has multiple Ø2.50" knockouts on the sides, rear, and bottom that accommodate Ø2.00" conduit fittings. See Figure 2 for knockout locations.

#### 3.9. Conduit Seals

All internal and external conduit openings on the CUBE must be completely sealed with a duct seal compound to prevent moisture from entering the equipment compartment. Use a moldable, flame-retardant putty style duct seal material. Do not use an expanding foam seal. Mold the putty so that the open space around the wire or conduit is completely sealed, as shown in Figure 10. If the openings must be accessed at any time, remove the putty and set it aside. When work is complete, re-mold the putty to re-seal the opening.

## 3.10. Verifying the Installation

Verify that earth ground and all grounding and bonding is complete and functional. After verifying that all installer connections are secure and complete, apply voltage.




Figure 10 Applying Putty Seal

#### 4. PERIODIC MAINTENANCE

In the event that the enclosure must be opened in freezing conditions, use a narrow, pointed metallic object such as a screwdriver or chisel, along with a non-metallic device like a rubber mallet, to remove excessive ice buildup around the door and locking mechanism. A commercial aerosol de-icer spray can be used to free up locks and latches if needed. Use protective gloves and safety glasses when applying de-icer sprays.

Reset the GFCI duplex receptacle periodically to ensure it is working. The unit meets UL-943, which requires an auto-monitoring (self-testing) feature. A flashing or solid red LED indicates a fault. If the unit continues to show a fault after resetting, replace the unit.

Refer to the HVAC manual supplied with the HVAC for periodic maintenance requirements.

#### 5. TECHNICAL ASSISTANCE AND REPAIR SERVICE

For questions on product repair or if technical assistance is required, contact Charles Technical Support.

847-806-8500

techserv@charlesindustries.com (email)

http://www.charlesindustries.com/techserv.htm

#### 6. WARRANTY & CUSTOMER SERVICE

Charles Industries LLC offers a one-year warranty on the CUBE product. The Charles warranty is limited to the operation of the CUBE hardware as described in this documentation and does not cover equipment that may be integrated by a third party. The terms and conditions applicable to any specific sale of product shall be defined in the resulting sales contract. For questions on warranty or other customer service assistance, contact your Charles Customer Service Representative.

847-806-6300

mktserv@charlesindustries.com (email)

http://www.charlesindustries.com/main/telecom sales support.htm

2<sup>nd</sup> Printing Page 9 of 11



## 7. SPECIFICATIONS

# 7.1. Regulatory Specifications

- Designed to meet GR-487
- UL-2416 Listed
- GFCI: UL-943 Listed

If CUBEs are field-modified, a customer provided ETL field evaluation of the modified components may be required to re-establish ETL certification to UL standards. Consult local jurisdictions for guidance on a site-by-site basis.

## 7.2. Product Specifications

Physical				
Dimensions	74"Hx32"Wx32"D			
Weight	Approx. 775 lbs. as shipped			
23" Equipment Rack Space and Hole Spacing	68.25" (39RU) rack spacing with tapped EIA #12-24 mounting holes			
Maximum Supported Weight	Rack Rails: 429 lbs.			
Materials	0.125" aluminum			
Color	Off-white			
Electrical				
UPS	APC SMX2000LVNC			
Battery Pack	APC SMX120BP			
AC Load Center	Square D QO112L125PGRB			
AC Surge Suppressor	Eaton ZD16731LN			
Bonding and Grounding	(2) 2x8 position internal ground bars, external grounds on sides and rear			
Cable Entry	See Figure 2 or section 3.8.6			
Thermal				
HVAC System	115VAC, Dantherm			
Cooling Capacity	4000BTU			
Environmental				
Operating Temp. Range, Outside Enclosure	-40° to +115°F, -40° to 46°C			
Operating Temp Range, Inside Enclosure	-40° to +149°F, -40° to 65°C			
Humidity	0 to 95% (non-condensing)			
Altitude	Up to 2,000 meters (6560 feet)			
Kits and Replacement Parts				
Touch-up Paint	02-000290-0			
216 Type Security Tool	07-002070-0			
Replacement Gasket	80-006688-A			
Shim Kit for Leveling	97-000010-0			
Lift-Up Handle	39-000335-0			
Door Rod Latch	39-000336-0			
2-Wire Door Alarm Switch	17-400322-0			
HVAC Cutoff Switch	17-400329-0			
GFCI Outlet	15A, 04-100207-0			
AC Outlet	20A, 04-100225-0			
Overheat Thermostat	99-004548-0			

Table 1 CUBE Specifications

Page 10 of 11 2<sup>nd</sup> Printing



## 7.3. Macro Alarm Panel Connections

Alarm Number	Description
CC1	Door Intrusion
CC2	Commercial Power Failure
CC3	Surge Suppressor/Lightening Arrestor
CC4	Rectifier Failure
CC5	Multiple Rectifier Failure
CC6	Battery Discharge
CC7	Low Voltage
CC8	DC Power Failure
CC9	Generator Running
CC10	Generator Low Fuel
CC11	Generator Failure
CC12	HVAC Failure
CC13	High Temp
CC14	Low Temp
CC15	Tower Light
CC16	Tower Light Side
CC17	RRH Up-Convertor Failure
CC18	RRH Power Failure
CC19	RRH High Humidity
CC20	RRH Intrusion
CC21	Smoke/Fire
CC22	Bus Bar Theft
CC23	Battery Breaker Alarm
CC24	
CC25	Microwave Critical
CC26	Microwave Major
CC27	Dehydrator Alarm
CC28	Fire Suppression Discharge
CC29	Fire Suppression Trouble
CC30	Secondary HVAC Running
CC31	Explosive Gas
CC32	High Humidity

Table 2 Macro Alarm Wiring Table

2<sup>nd</sup> Printing Page 11 of 11